



# UAB Campus Tree Care Plan

I.	Purpose
II.	Responsible Authority2
III.	Committee2
IV.	Tree Care Policies
V.	Protection and Preservation Policies
VI.	Goals and Targets
VII.	Tree Damage Assessment
VIII.	Prohibited Practices
IX.	Terminology14
X.	Communication Strategy14
XI.	Facilities Standard for Landscape/Hardscape Protection Appendix A
XII.	Tree Hazard Evaluation FormAppendix B



# 1. Purpose

The UAB Campus Tree Care Plan exists to:

Protect, promote, and preserve existing trees on UAB's campus, while providing guidelines to encourage the addition of campus green spaces, in order to create a more attractive, healthy, and sustainable campus. This tree care plan is intended to act as a reference point in assisting the coordination between developers, landscapers, campus planners, and the general campus population, in order to ensure that related policies are upheld while maintaining the integrity of the trees on the UAB campus.

# 2. Responsible Authority

The Campus Tree Care Plan will be enforced by the Associate Vice President for Facilities Management.

# 3. Committee

The University of Alabama at Birmingham Campus Tree Advisory Committee was established as part of the Tree Campus USA initiative developed by the National Arbor Day Foundation. The committee consists of members of the faculty, staff and student groups, and also a member of the Birmingham community. The committee shall meet a minimum of twice per year, and additionally as needed. Each member will serve a 2 year term with option to renew as approved by the Chairperson (Manager, Campus Services and Grounds). The Committee will participate in annual reviews of the Tree Care Plan, and provide support for projects related to trees and green spaces on campus.

Members:

<u>Facility Management</u> Tim Sullivan, Chairperson Manager, Campus Services and Grounds <u>grasso@uab.edu</u>

## Faculty

Stephen Watts, Ph.D. Biology Professor <u>sawatts@uab.edu</u>

## Staff

Julie Price, Ph.D. Sustainability Coordinator juliegp@uab.edu

## John Nagy

Senior Instructional Design Specialist, School of Health Professions nagy2@uab.edu

## Students

Sarah Griffin

Political Science and Philosophy Majors saegriff@uab.edu

## Community Partners

#### Henry Hughes

Director of Education, Birmingham Botanical Gardens <u>hhughes@bbgardens.org</u>



# 4. Tree Care Policies

# **UAB Specifications for Tree Insect Control**

Sites:

Annual campus-wide applications to young trees (3"-5.5" inch in caliber).

Task:

Apply preventative insect control oil treatment to target eggs, larvae, and or insects on young trees 3"-5.5" inch in caliber to control the population of harmful scale insects.

Specifications and Frequencies:

1 treatment with horticultural oil applied at the appropriate label rate for the host plant applied in January during the appropriate temperature range.

## Justification:

Insects, in particular scale insects, in our urban conditions threaten younger smaller trees. Scale insects use sucking mouth parts to extract juices from trees and weaken them to the point of death and or functional demise. Horticultural oils applied to dormant trees suffocates scale eggs, larvae, and insects. It is a safe, environmentally-friendly control method.

## **UAB Tree Replacement Plan**

Scope: The intention of this tree replacement plan is to provide sustainable tree replacements for trees which require removal for non-construction or development reasons. Tree removals are sometimes necessary due to age, health, structural integrity, physical damage, construction, control efforts for evasive or non-native species, and emergencies.

- \* Rates: The replacement rate for lost trees is two trees replaced for every one tree lost. Removal sites and replacement sites may not necessarily be the same due to space limitations.
- \* Timing: The horticultural window of opportunity for tree replacement shall follow a reasonable annual horticultural time frame typically November through Mid-February.
- \* Species: The replacement species shall be chosen based on the short- or long-term use of the site, the best horticultural selection, and design match for the site. The replacement species may not necessary be the same as the removal species.





## **General Selection Criteria**

- UAB should encourage the selection of trees appropriate for a particular urban site. Tree placement should consider energy saving values, nearby power lines, and root characteristics.
- Trees used for new plantings in urban areas should be selected primarily from species with low water requirements.
- Where appropriate, trees that benefit urban wildlife species by providing food or cover should be incorporated in urban plantings.

### **Campus Standards for Planting New Trees:**

- (a) Standard
- (b) Standard (2)
- (c) Evergreens
- (d) Standard on a slope
- (e) Evergreen on a slope
- (f) Drainage
- (g) Shrubs
- (h) Sidewalk consideration
- (i) Multi trunk



THE UNIVERSITY OF

ALABAMA AT BIRMINGHAM





**Facilities Division** 

(c)



(e)



(f)



#### **Facilities Division**

(g)



LABALABAMA AT BIRMINGHAM

**Facilities Division** 

(i)



**Approved Species for UAB** Flowering

UAB Campus Tree Care Plan

**Facilities Division** 

#### **BOTANICAL NAME**

Amelanchier arborea Amelanchier x 'Autumn Brilliance' Cercis Canadensis Cercis canadensis 'alba' Chionanthus virginicus Cornus florida 'Cherokee Princess' Cornus kousa Cotinus coggyria Crataegus Phaenopyrum Franklinia alatamaha Halesia carolina Hammelis mollis Lagerstroemia indica 'Byer's White L indica 'Choctaw' L indica 'Miami' L indica 'Tuscarora' L indica Victor' L indica 'Natchez' L indica 'Watermelon Red'Watermelon L indica 'William Toovey' M soulangiana 'Alba' Magnolia macrophylla Magnolia soulangiana Magnolia stellata Malus floribunda 'Calloway' Philadelphus coronaries Prunus autumnalis Prunus yedoensis

#### **COMMON NAME**

Serviceberry Autumn Brilliance Serviceberry Redbud White Redbud Fringe Tree Cherokee Princess Dogwood Kousa Dogwood Smoketree Washington Hawthorn Franklinia Carolina Silverbell Chinese Witch-Hazel Byer's White Crape Myrtle Choctaw Crape Myrtle Miami Crape Myrtle Tuscarora Crape Myrtle Victor Crape Myrtle Natchez White Crape Myrtle Red Crape Myrtle William Toovey Crape Myrtle White Saucer Magnolia **Bigleaf** Magnolia Saucer Magnolia Star Magnolia Calloway Crabapple Mock Orange Autumnalis Cherry Yoshino Cherry

**Facilities Division** 

Deciduous

### **BOTANICAL NAME**

Acer barbatum Acer buergeranum Acer palmatum Acer palmatum 'Atropurpureum' A, palmatum 'Dissectum' A palmatum 'Burgundy Lace' Acer rubrum 'October Glory A rubrum 'Autumn Sunset' Carpinus caroliniana Celtis laevigata Fagus grandifolia Fraxinus americana Fraxinus pennsylvanica 'Marshall' Fraxinus pennsylvanica 'Urbanite' Ginkgo biloba Liriodendron tulipifera Nyssa sylvatica Pistacia chinensis Quercus acutissima Quercus alba Quercus laurifolia Quercus lyrata Quercus nuttalli Quercus phellos Quercus prinus Quercus shumardi Taxodium distichum Ulmus parvifolia Ulmus parvifolia 'Emer I' Ulmus parvifolia 'Emer II' Zelkova serrata

### **COMMON NAME**

Southern Sugar Maple **Trident Maple** Japanese Maple Threadleaf Maple **Dissectum Japanese Maple** Burgundy Lace Jap Maple October Glory Red Maple Autumn Sunset Red Maple American Hornbeam Sugar Hackberry American Beech White Ash Marshall Ash Urbanite Ash Ginkgo **Tulip Poplar** Black Gum **Chinese** Pistache Sawtooth Oak White Oak Laurel Oak **Overcup Oak** Nuttall Oak Willow Oak Chestnut Oak Shumard Oak **Bald Cypress** Chinese Elm Athena lacebark Elm Allee lacebark Elm Japanese Zelkova

**Facilities Division** 

Evergreen

## **BOTANICAL NAME**

Ilex cornuta 'Bufordii' Ilex opaca Ilex X attenuata 'East Palatka' Ilex X 'Nellie R Stevens' Ilex X 'Fosterii' *Ilex vomitoria* Ilex vomitoria 'Pendula' *Ligustrum japonicum* Magnolia grandiflora Magnolia grandiflora 'Bracken Brown Beauty' Magnolia grandiflora 'Claudia Wannamaker' Magnolia grandiflora 'Green Giant' Magnolia grandiflora 'Little Gem' Magnolia virginiana Magnolia x'Ann' Magnolia x 'Full Eclipse' *Myrica cerifera* Osmanthus americanus Pinus glabra Pinus strobus Pinus taeda Pinus virginiana Quercus acuta *Quercus laurifolia Quercus virginiana* Tsuga canadensis

# COMMON NAME

**Burford Holly** American Holly East Palatka Holly Nellie Stevens Holly Foster #2 Holly Yaupon Weeping Yaupon Wax leaf Ligustrum Southern Magnolia Bracken Brown Beauty Magnolia Claudia Wannamaker Magnolia Southern Magnolia Little Gem Magnolia Sweet Bay Magnolia Ann Magnolia Full Eclipse Magnolia Wax Myrtle Devilwood Spruce Pine White Pine Loblolly Pine Virginia Pine Japanese Evergreen Oak Laurel Oak Live Oak Canadian Hemlock



## **Managing for Catastrophic Events**

For catastrophic events such as severe weather, fallen or hazardous trees and associated debris will be removed by Campus Services and Grounds personnel or an outside tree company. The cleanup will be prioritized to maintain critical access for police, fire department, hospital buildings, and roadways first.

# 5. Protection and Preservation Policies For all Construction Projects

- Facilities Standard Number 02802 for Landscape/Hardscape Protection During Construction (Appendix A) is the guiding document for policies during construction related to trees, in addition to the statements below.
- Prior to the issuance of any approval or permit, all trees on the site shall be inventoried by the Landscape Architect, including size, species, location, and photos. The inventory shall be submitted to the Manager of Campus Services and Grounds.
- Any pruning done to accommodate a work site shall be performed by, or under the direction of, Campus Services and Grounds personnel.
- Six-foot chain link fence barricades shall be installed prior to construction to cover as much ground as possible outside the tree drip line. If more space is needed inside the drip line, barriers should not be inside of the tree critical root radius defined as the product of (the tree trunk's diameter in inches at height of 4.5 ft) x 1.5, expressed in feet.
- No construction equipment, vehicles, offices, or materials shall be stored, parked or standing within the tree drip line.
- Wires, signs, and other similar items shall not be attached to trees.
- Drains shall be installed according to city specifications so as to avoid harm to trees due to excess water.
- No waste construction materials or wastewater (paint thinner, paints, cement rinsing, etc) shall be dumped on the ground or into any grate between the drip line and the base of the tree or uphill from any tree where certain substances might reach the roots.
- Cutting and filling around the base of trees shall be done only after consultation with the Landscape Architect and UAB Campus Services and Grounds.
- Trenching Wherever cuts are made in the ground near the roots of trees, appropriate measures shall be taken to prevent exposed soil from drying out and causing damage to tree roots. When possible, utilities should be run around the drip line of the tree, to avoid critical damage. In some cases, boring may be used to avoid trenching.
- Damage to any tree during construction shall be reported to UAB Campus Services and Grounds, and the contractor shall pay to treat the tree for damage in the manner specified by the Landscape Architect and Campus Services and Grounds.

**Facilities Division** 

# 6. Goals and Targets Goals with Associated Targets

1. **Goal:** <u>UAB should continue to support programs that encourage the engagement of interested citizens in the value of urban trees.</u>

Target: Plan and implement Arbor Day 2015 celebration.

2. **Goal:** Development projects should include the preservation of significant trees. Any adverse effect on the health and longevity of significant trees should be avoided through appropriate design measures and construction practices. When tree preservation is not feasible, the significant tree will be appraised by a certified arborist using *The Guide for Plant Appraisal*, 9<sup>th</sup> Edition to develop a supported estimate of current value. This amount shall be transferred into the UAB Tree Fund. Funds from site development tree removal can be put back into the same site's redevelopment for tree planting as space permits. Remaining funds from each development project will remain in the fund to be used for planting other trees and tree maintenance.

Target: Establish the UAB Tree Fund.

# 7. Tree Damage Assessment

Trees are evaluated for any risks they pose, using the Tree Hazard Evaluation Form (Appendix B). Damage is remedied through a combination of pruning, treatments, or removal if deemed necessary. Intentional damage caused during construction will be addressed as described in section 5 of this document.

# 8. Prohibited Practices

1. It is prohibited to attach signs to trees.

(Birmingham Ordinance No. 1809-F, Title 3, Article VI, Section 9, Subsection 3, Item 3, Part f)It is prohibited for any person to break, cut, injure, remove, burn, pull, or otherwise damage any tree located on any part of UAB campus.

- 3. It is prohibited to chain bikes to trees on campus.
- 4. Topping, heading, hat-racking, or any other form of inappropriate crown/branch reduction pruning shall not be permitted except in emergency situations or in executing a crown restoration procedure.
- 5. Under no condition shall a tree be planted on UAB campus for dedication without pre-approval and consultation with UAB Campus Planning.

#### **Facilities Division**

- 9. Terminology
- <u>Arboriculture</u> is the cultivation, management, and study of individual trees, shrubs, vines, and other perennial woody plants
- <u>Caliper</u> The diameter or thickness of the main stem of a young tree or sapling as measured at six (6") inches aboveground level.
- <u>Development</u> The act, process or state of erecting buildings or structures, or making improvements to a parcel or tract of land
- <u>Drip line</u> The area defined by the outermost circumference of a **tree** canopy where water drips from onto the ground
- <u>Green space</u> Any area retained as permeable unpaved ground and dedicated on the site plan to supporting vegetation.
- <u>Multi-stem trees</u> all tree stems shall be measured at two feet above the ground, the sum of all these measurements equals the diameter of the tree for ordinance and mitigation purposes.
- <u>Native tree</u> Any tree species which occurs naturally and is indigenous within the region.
- <u>Trenching</u> The process of digging long, narrow channels in the ground for the purpose of laying pipes and wires during construction projects.

# **10.**Communication Strategies

This plan will be available through the UAB Facilities website. It is meant to be accessible to developers, landscapers, campus planners, and the general campus population.





#### Appendix A

# UNIVERSITY OF ALABAMA AT BIRMINGHAM

DEPARTMENT OF FACILITIES PLANNING

# FACILITIES STANDARD

NAME: Landscape/Hardscape Protection During Construction NUMBER: 02802 ORIGINAL DATE: 04-Jun-2003 REVISION DATE: 26-Feb-2007

#### PURPOSE:

- The general purpose of each Facilities Standard is to provide minimal criteria for construction materials at University facilities regarding code compliance, warranty, approved products, execution, and uniformity.
- To protect the health and safety of patients, visitors, students, faculty, and staff, in addition to protecting non-project UAB property, all construction must be in accordance with NFPA 241 safeguarding construction, alteration, and demolition operations; Standard Building Code, Chapter 33, regarding site work, demolition, and construction; NFPA 101 Life Safety Code.
- Construction safety is the responsibility of the contractor in accordance with the regulations and codes of the agency having jurisdiction, and according to the guidelines adapted by OSHA.
- 4. The Landscape/Hardscape Protection During Construction Facilities Standard establishes a series of guidelines for specifying this particular item on any construction project at the University. This Facilities Standard is not to be regarded as a specification.

#### EXECUTION:

- 1. Protection of Hardscape Materials:
  - A. Pre-construction inventory photos of hardscapes are required prior to construction to document the pre-construction conditions.
  - B. Hardscape protection measures, such as covering sidewalks, curbs, pavers, etc. with plate steel, plywood, or other materials, to disperse weight and prevent damage from construction vehicles should be applied. Access to and from the construction site should be defined and limited.
  - C. Protection measures such as barriers, removing light poles, signs, etc. to prevent damage.
- Protection of Landscape Materials:
  - A. Pre-construction inventory photos of landscapes are required prior to construction to document the pre-construction conditions.
  - B. Campus Services and Grounds personnel determine if any plant material can be salvaged and relocated based on the time of year, condition, size, species, and/or monetary or historical value of the material.

DEVELOPED BY AND INTENDED FOR UAB USE ONLY NOT FOR OUTSIDE DISTRIBUTION PAGE NO. 02802.1

# LABARAMA AT BIRMINGHAM

#### **Facilities Division**

	E: Landsca SER: 0280	pe/Hardscape Protection During Construction ORIGINAL DATE: 04-Jun-2003 2 REVISION DATE: 28-Feb-2007				
	C.	Any pruning done to accommodate a work site shall be performed by, or under th direction of, Campus Services and Grounds personnel.				
	D.	All plant materials to remain in the construction zone shall be protected to prever damage and cared for according to species requirements.				
3.	Prote	ection of Irrigation Materials:				
	Α.	Irrigation systems protection measures such as burying heads, covering valves identifying pipe locations, etc., are required prior to construction to prevent damage t wiring, piping, heads, valves, controllers, back flow prevention devices, etc.				
4.	Protection of Trees:					
	A.	Protection barriers, defined as six-foot chain link fencing, shall be installed prior to construction and shall cover as much ground as possible outside the tree's drip line. If more space is needed inside the drip line, barriers should not be inside of the tree's critical root radius defined as the product of (the tree trunk's diameter in inches at a height of 4.5 feet) x 1.5, expressed in feet.				
	В.	Limit construction machine access, material storage, chemical and cement rinsing, and vehicle parking and office sites to non-tree areas.				
		END OF STANDARD				
Prepar	ed by:	Image: Campus Services Reviewed and Recommended by: Hope Hammonds   Director, Design Build Services Director, Design Build Services				
	ved and mmended by	Mark & Goska Architect, Health Facilities Approved by: Mark A. Goska Architect, Health Facilities				



# Appendix B

Mapf.oction:	Site/Address:	HAZARD RATING:
Owner: public   private   unknown   other   Petential of part Rating Rating Rating Date:   Immediate action needed Needs further inspection     Date of last inspection:		
Date		
Date of usis inspection:	Date: Inspector:	Immediate action needed
TREE CHARACTERISTICS	Date of last inspection:	
Tree #:   Species:     DBH:   # of trunks:   Height:   Spread:     Form:   generally symmetric   Inition asymmetry   major asymmetry   stump sprout   stag-headed     Crown class:   dominant   co-dominant   Intermediate   suppressed     Live crown ratic:	TREE CHARACTERISTICS	Dead tree
Form:   generally symmetric   minor asymmetry   major asymmetry   stupp sprout   stag-headed     Crown class:		
Crown class:   dominant   intermediate   suppressed     Live crown ratio:   %   Age class:   young   semi-mature   mature   over-mature/senescent     Pruning history:   crown cleaned   excessively thinned   topped   crown raised   pollarded   crown reluced   flush cuts   cabled/braced     Bonone   multiple pruning events   Approx. dates:	DBH: # of trunks: Height: Spread:	
Live crown ratio:	Form:	prout 🗆 stag-headed
Pruning history:   crown cleaned   excessively thinned   topped   crown reided   flush cuts   cabled/braced     Special Value:   specimen   heritage/historic   wildlife   unusual   street tree   screen   shade   indigenous   protected by gov. ager     TREE HEALTH	Crown class:	
In one   Imultiple pruning events   Approx. dates:     Special Value:   specimen   heritage/historic   wildlife   unusual   street tree   screen   shade   Indigenous   protected by gov. age     TREE HEALTH	Live crown ratio: % Age class: 🗆 young 🗆 semi-mature 🗆 mature 🗌	] over-mature/senescent
TREE HEALTH		
Foliage color:   normal   chlorotic   Epicormies?   Y   N   Growth obstructions:     Foliage density:   normal   sparse   Leaf size:   normal   small   stakes   wire/ties   signs   cables     Annual shoot growth:   excellent   average   poor   Twig Dieback?   Y   N   curb/pavement   guards     Woundwood development:   excellent   average   fair   poor   none   other	Special Value:	reen 🗆 shade 🗆 indigenous 📄 protected by gov. age
Foliage color:   normal   chlorotic   Epicormies?   Y   N   Growth obstructions:     Foliage density:   normal   sparse   Leaf size:   normal   small   stakes   wire/ties   signs   cables     Annual shoot growth:   excellent   average   poor   Twig Dieback?   Y   N   curb/pavement   guards     Woundwood development:   excellent   average   fair   poor   none   other	TREE HEALTH	
Annual shoot growth:   excellent   average   poor   Twig Dieback?   Y   N   curb/pavement   guards     Woundwood development:   excellent   average   poor   none   other		Growth obstructions:
Woundwood development:   excellent   average   poor   none   other     Vigor class:   excellent   average   fair   poor     Major pests/diseases:	Foliage density: 🗆 normal 🗆 sparse 🛛 Leaf size: 🗆 normal 🗔 small 🛛	🗆 stakes 🛛 wire/ties 🗆 signs 🖾 cables
Vigor class:   excellent   average   fair   poor     Major pests/diseases:	Annual shoot growth: 🗆 excellent 🗆 average 🗆 poor 🏾 Twig Dieback? Y N 👘	□ curb/pavement □ guards
Major pests/diseases:     STEE CONDITIONS     Site Character:   residence     commercial   industrial   park   open space   natural   woodlandVorest     Landscape type:   parkway   raised bed   container   mound   lawn   shrub border   wind break     Irrigation:   none   adequate   inadequate   excessive   trunk wettled     Recent site disturbance?   Y   N   construction   soil disturbance   grade change   line clearing   site clearing     % dripline paved:   0%   10-25%   25-50%   50-75%   75-100%   Pavement litted?   Y   N     % dripline grade lowered:   0%   10-25%   25-50%   50-75%   75-100%     % dripline grade lowered:   0%   10-25%   25-50%   50-75%   75-100%     Soil problems:   chanage   shallow   compacted   droughty   saline   alkaline   acidic   small volume   disease center   history of fail	Woundwood development: 🗆 excellent 🗆 average 🗆 poor 🗆 none	] other
SITE CONDITIONS     Site Character:   lesidence   commercial   industrial   park   open space   natural   woodlandVorest     Landscape type:   parkway   laised bed   container   mound   lawn   shrub border   wind break     Irrigation:   none   adequate   inadequate   excessive   trunk wettled     Recent site disturbance?   Y   N   construction   soil disturbance   grade change   line clearing   site clearing     % dripline paved:   0%   10-25%   25-50%   50-75%   75-100%   Pavement lifted?   Y   N     % dripline w/ fill soil:   0%   10-25%   25-50%   50-75%   75-100%     % dripline grade lowered:   0%   10-25%   25-50%   50-75%   75-100%     Soil problems:   drainage   shallow   compacted   droughty   saline   alkaline   acidic   small volume   disease center   history of fail		
Site Character:   Image: Ima	Major pests/diseases:	
Landscape type:   parkway   raised bed   container   mound   lawn   shrub border   wind break     Irrigation:   none   adequate   inadequate   excessive   trunk wettled     Recent site disturbance?   Y   N   construction   soil disturbance   grade change   line clearing   site clearing     % driptine paved:   0%   10-25%   25-50%   50-75%   75-100%   Pavement lifted?   Y   N     % driptine grade lowered:   0%   10-25%   25-50%   50-75%   75-100%     % driptine grade lowered:   0%   10-25%   25-50%   50-75%   75-100%     Soil problems:   drainage   shallow   compacted   droughty   saline   alkaline   acidic   small volume   disease center   history of fail	SITE CONDITIONS	
Irrigation:   none   adequate   inadequate   excessive   trunk wettled     Recent site disturbance?   Y   N   construction   soil disturbance   grade change   line clearing   site clearing     % dripline paved:   0%   10-25%   25-50%   50-75%   75-100%   Pavement lifted?   Y   N     % dripline grade lowered:   0%   10-25%   25-50%   50-75%   75-100%     % dripline grade lowered:   0%   10-25%   25-50%   50-75%   75-100%     Soil problems:   clarainage   shallow   compacted   droughty   saline   alkaline   acidic   small volume   disease center   history of fail	Site Character:	natural woodland\forest
Recent site disturbance?   Y N   construction   soil disturbance   grade change   line clearing   site clearing     % dripline paved:   0%   10-25%   25-50%   50-75%   75-100%   Pavement lifted?   Y N     % dripline w/ fill soil:   0%   10-25%   25-50%   50-75%   75-100%     % dripline grade lowered:   0%   10-25%   25-50%   50-75%   75-100%     Soil problems:   drainage   shallow   compacted   droughty   saline   alkaline   acidic   small volume   disease center   history of fail	Landscape type:	shrub border 🛛 wind break
% dripline paved:   0%   10-25%   25-50%   50-75%   75-100%   Pavement lifted? Y N     % dripline w/ fill soil:   0%   10-25%   25-50%   50-75%   75-100%     % dripline grade lowered:   0%   10-25%   25-50%   50-75%   75-100%     % dripline grade lowered:   0%   10-25%   25-50%   50-75%   75-100%     Soil problems:   drainage   shallow   compacted   droughty   saline   alkaline   acidic   small volume   disease center   history of fail      Obstructions:   lights   signage   line-of-sight   view   overhead lines   underground utilities   traffic   adjacent veg.	Irrigation:	
% dripline yrite:   0%   10-25%   25-50%   50-75%   75-100%     % dripline grade lowered:   0%   10-25%   25-50%   50-75%   75-100%     Soil problems:   drainage   shallow   compacted   droughty   saline   alkaline   acidic   small volume   disease center   history of fail      clay   expansive   slope    aspect:		
% dripline grade lowered:   0%   10-25%   25-50%   50-75%   75-100%     Soil problems:   drainage   shallow   compacted   droughty   saline   alkaline   acidic   small volume   disease center   history of fail		Pavement lifted? Y N
Soil problems:   drainage   shallow   compacted   droughty   saline   alkaline   acidic   small volume   disease center   history of fail		
Clay   expansive   slope   ° aspect:		dir. 🗋 small volume 🗋 disease center. 🗖 history of fai
Obstructions:   lights   signage   line-of-sight   view   overhead lines   underground utilities   traffic   adjacent veg.		
Prevailing wind direction: Occurrence of snow/ice storms		ground utilities 🛛 traffic 🔲 adjacent veg. 🗆
TARGET		
Use Under Tree: Duilding Darking Traffic Dedestrian recreation Dandscape Ardscape small features Utility lines	Exposure to wind: Single tree below canopy above canopy recently exposed [	seldom regularly
Use Under Tree: Duilding Darking Dtraffic Dedestrian Drecreation Dlandscape Ardscape Small features Dutility lines	and the second	
	Prevailing wind direction: Occurrence of snow/ice storms	
	Prevailing wind direction: Occurrence of snow/ice storms	upe □ hardscape □ small features □ utility lines
	Prevailing wind direction:   Occurrence of snow/ice storms   never   Image: Constraint of the store stor	npe □ hardscape □ small features □ utility lines

-



4 =

THE UNIVERSITY OF ALABAMA AT BIRMINGHAM

		-1		
ROOT DEFECTS:				
suspect root rot: Y N Mu	shroom/conk/bracket presen	E Y N ID:		
xposed roots: Severe	] moderate 🛛 low 🛛 U	Indermined: 🗆 severe 🗖	moderate low	
toot pruned: distance	o from touck Doot area a	ffoctod: % Butt	ress wounded: Y N W	/hen:
testricted root area: D sever	e 🗆 moderate 🗆 low	Potential for root failure:	severe moderate E	low
EAN: deg. from ver	tical 🗆 natural 🗆 unnat	ural self-corrected So	il heaving: Y N	
Decay in plane of lean: Y N				
Compounding factors:			Lean severity: 🛛 sev	vere 🛛 moderate 🖾 low
CROWN DEFECTS: Indicate pres	sence of individual defects and	I rate their severity (s = severe, r	m = moderate, I = low)	
DEFECT	ROOT CROWN	TRUNK	SCAFFOLDS	BRANCHES
Poor taper				
Bow, sweep		- A		
Codominants/forks				
Multiple attachments				
Included bark				
Excessive end weight				
Cracks/splits				
Hangers				
Girdling				1.
Wounds/seam				
Decay				
Cavity				
Conks/mushrooms/bracket				
Bleeding/sap flow				
Loose/cracked bark				
Nesting hole/bee hive				
Deadwood/stubs				
Borers/termites/ants				
Cankers/galls/burls				
Previous failure				
HAZARD RATING				
Tree part most likely to fail:			Failure potential: 1 - low	; 2 - medium; 3 - high; 4 - severe
			Size of part: 1 - <6" (15	cm); 2 - 6-18" (15-45 cm);
Inspection period: a				45-75 cm); 4 - >30" (75 cm)
Failure Potential + Size of Part +	2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2		Target rating: 1 - occasio	onal use; 2 intermittent use;
++	=		3 - freque	nt use; 4 - constant use
HAZARD ABATEMENT				
Prune: remove defective p	oart 🔲 reduce end weight	□ crown clean □ thin □ rai	se canopy Crown reduce	restructure shape
Cable/Brace:		Ir	nspect further: D root crown	🗆 decay 🔲 aerial 🔲 monit
Remove tree: Y N Repl	ace? Y N Move targe	et: Y N Other:		
Effect on adjacent trees:				
Effect on adjacent trees:				

